Request for Bids - for Security Camera System

Lisbon CSD, Lisbon, IA will accept bid proposals from qualified vendors for a security camera system upgrade as described below:

All work pursuant to this contract shall be contingent upon state safety and security grant funding. The system must provide functionality to meet the district's needs. All equipment should be new. A system that meets are based needs is listed below. We will be looking to award bids to the most cost-effective total solution. All hardware bids must be NDAA compliant. Bids with hardware that are not compliant will not be considered.

Camera System Project

Successful bidders will issue a bid that contains the following information. Price for the following

Middle School & District Cameras

- Quantity (3) Axis P3738-PLE Panoramic Camera
    - Part Number - 02635-001
- Quantity (1) P1468-LE Bullet Camera
    - Part Number - 02342-001
- Quantity (2) P4707-PLVE Panoramic Camera
    - Part Number - 02416-001
- Quantity (5) Axis P4705-PLVE Panoramic Camera
    - Part Number - 02415-001
- Quantity (1) Axis P3267-LV Dome Camera
    - Part Number - 02329-001
- Quantity (3) Axis T94N01D Pendant Kit
    - Part Number - 01513-001
- Quantity (3) Axis T91d61 Wall Mount 1.5" NPS
    - Part Number - 5504-821
- Quantity (2) Axis T91A64 Corner Bracket
    - Part Number - 5017-641
- Quantity (2) Axis TP4601-E Conduit Back Box
    - Part Number - 02750-001
- Quantity (1) TP3603 2N IP Solo Flush (works with T94S01P)
    - Part Number - 02205-001
- Quantity (12) New Network Drops - Green Commscope - CAT6

High School Cameras
- Quantity (3) Axis P3738-PLE Panoramic Camera
  - Part Number - 02635-001
- Quantity (2) Axis P3267-LV Dome Camera
  - Part Number - 02329-001
- Quantity (3) P4707-PLVE Panoramic Camera
  - Part Number - 02416-001
- Quantity (6) Axis P4705-PLVE Panoramic Camera
  - Part Number - 02415-001
- Quantity (2) TP3603 2N IP Solo Flush (works with T94S01P)
  - Part Number - 02205-001
- Quantity (1) Axis TP4601-E Conduit Back Box
  - Part Number - 02750-001
- Quantity (40) Genetec 1 Omnicast Education Camera Connection for K12.
  - Part Number - GSC-EDU-OM-IC
- Quantity (14) New Network Drops - Green Commscope - CAT6

Elementary School Cameras
- Quantity (2) P4707-PLVE Panoramic Camera
  - Part Number - 02416-001
- Quantity (3) Axis P4705-PLVE Panoramic Camera
  - Part Number - 02415-001
- Quantity (2) Axis P3267-LV Dome Camera
  - Part Number - 02329-001
- Quantity (1) P1468-LE Bullet Camera
  - Part Number - 02342-001
- Quantity (1) Axis TP4601-E Conduit Back Box
  - Part Number - 02750-001
- Quantity (1) Streamvault 404EX Series 2U 28 Bay Appliance
  - 132 TB RAW RAID 6
  - 2 x Xeon Gold 5416S 64GB RAM
  - 2 x 480 GB m.2 SSD
  - 11 x 12TB 3.5" Enterprise HDDs
  - Part Number - SV404EX-R28-132T-12-416
  - *Unless quoted cameras do not require on-prem server storage*
- Quantity (1) Genetec Security Center GSC Base Enterprise Package, Education Edition for K12
  - Part Number - GSC-EDU-BASE

- ○ Quantity (1) Security Center 5.12
  - ■ Part Number - GSC-5.12
- ○ Quantity (8) New Network Drops - Green Commscope - CAT6

- Price for installing the above equipment. Install includes data cabling to each location (number of drops specified above by building). Installation and labor needs to be broken out by building (Middle School / District, High School, and Elementary School). This is a total price for the project including labor, materials, configuration, and testing. The vendor is responsible for scheduling an onsite visit to determine if the current infrastructure will support the products being bid. If the vendor has already walked the building in the last 12 months, then no new visit is necessary.
- Record and/ or reference of successfully installing this product to Iowa K12 institutions.

Equivalent Products - *Equivalent products may be bid, but will need to match the specifications of the products listed above.* It is the responsibility of the bidder to supply a list of equivalent products and the matching specifications prior to approval. Otherwise the bid may not be accepted.

All bids should include the necessary hardware to complete the project. This should include but not be limited to J-hooks, modular jacks, wire mold, and fire sleeves. Panduit, ICC and GenSpeed are all acceptable cable brands to use. If you would like to use a different brand that will need to be cleared with the district pre-bid. All ends should be Panduit.

Note - Lisbon CSD will not be providing lifts, ladders, or other equipment for this installation.

For technical questions please contact Cameron Eichhorn - ceichhorn@lisbon.k12.ia.us and John Wyman - jwyman@gwaea.org

All bids are due by 4 pm November 25, 2024 - bids should be sent to Lisbon Community School District - securitygrant@lisbon.k12.ia.us